BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31092

APPROVED SCHEDULE - B

No. E/BTP/BBMP/E-PMT/02/2018-19, Date: 26.07.2018

Desilting of drains in Muneshwara Block and surrounding area in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of CHIRANJEEVI C ( )	
				In Figures	In Words
1	1674	Removing & Refixing stone slabs of drains and pointing in CM 1:3) (Page No. 25,Item No. 5.33)	Sqm	70.63	Rupees Seventy and Sixty Three Paise Only
2	1885.35	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. (Page No.141, Item No.19.1)	Cum	76.2	Rupees Seventy Six and Twenty Paise Only
3	1885.35	Conveying the excavated debries and over burden earth etc., to a lead of 10.00 Km distance by using private vehicle this includes the cost of loading and unloading charges etc., complete	Cum	92.93	Rupees Ninety Two and Ninety Three Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

22/10

22/10